

ID	Division	Parish / Town Council	Location	Scheme	Problem	Justification / Comments	Requested By	Estimated Cost (£)	Estimated Timescale Assuming smooth progress	RAG	
1	BH&LS	Buckhurst Hill	Roding Lane/Loughton Way, Buckhurst Hill	Pedestrian facilities at signal junction. Feasibility study agreed. Or alternatively pedestrian refuge to aid crossing of signalised junction and Vehicle Activated Signs.	Difficulty crossing road	It is not considered entirely necessary that a crossing is installed at this location, as a facility already exists on the desire line. However, pedestrians to the east of Loughton Way are still required to cross Loughton Way to reach the existing pedestrian crossing. It is therefore suggested that pedestrian facilities are considered as part of the signal controlled junction on Loughton Way and possibly Roding Lane. However further investigation would be necessary to ensure that the provision of a pedestrian phase would not cause excessive delay and congestion at the signals.	Historic scheme list	£5,000 feasibility study agreed ; Indicative Scheme costs £200,000 signal design and implementation	9 months	Amber	
2	BH&LS	Buckhurst Hill	Westbury Road/Palmerston Road/, Buckhurst Hill	Review of all traffic measures put in place	Mini-roundabout is perceived unsafe with one way road. See also Amberley Road / Russell Road.	Local opposition to one way road. High and unequal flows create confusion. They need also to look left to check nothing is coming out of the upper part of Westbury Rd or that anyone is using the pedestrian crossing beyond the roundabout. Residents, who live in the top half of Westbury Lane, want to turn right at the roundabout to access their road, and they tell me they are terrified because of fast traffic coming up the hill. May be benefit to review of area.	Historic scheme list	Feasibility study £5,000	6 months	Amber	
3	BH&LS	Buckhurst Hill	Farm Way/Forest Edge/Station Way, Buckhurst Hill	Traffic calming on Station Way/Farm Way, junction warning signs or VASs	Collision history / speeding on approaches	Previously AR site - lining improved. Following results of feasibility study a raised table was put forward as a traffic calming option.	Historic scheme list	£2K feasibility study Agreed & Raised table agreed £62,300	6 months	Red	
4	BH&LS	Buckhurst Hill	Station Way near LUL Station	Pedestrian refuge	Difficulty crossing road	Feasibility study recommended	New request	£2,000	TBC	Green	
5	IT368	BH&LS	Buckhurst Hill	Church Road / Russell Road / A121, High Road, Buckhurst Hill	Junction improvement	Unclear problem (congestion?), more information required	Install give way signs? Check accident stats. (pending validation)	Historic scheme list	2k	3 months	
6	BH&LS	Buckhurst Hill	Church Road/Stag Lane/Beech Lane	Traffic calming measures/One-way system	Narrow residential roads, affected by speeding traffic and parking. Three roads need to be looked at together.	Scheme requires validation 2012/13 with view to a scheme being implemented 2013/14	New request	TBC	TBC		
7	BH&LS	Loughton	Albion Hill, Loughton	One way road	Congestion	Likely to increase speeds / reduce road safety.	Historic scheme list	£3,500 Traffic Regulation Order	N/A	Red	
8	BH&LS	Loughton	Oakwood Hill j/w South View Road	Bollards across footway	Vehicles are routinely driving across the footway to avoid the four-way signals	Bollards are the best engineering solution	New request	£4K	4 months	Green	

ECC/ Epping Forest District Local Highways Panel										
ID	Division	Parish / Town Council	Location	Scheme	Problem	Justification / Comments	Requested By	Estimated Cost (£)	Estimated Timescale Assuming smooth progress	RAG
9	BH&LS	Loughton	A121 High Road (near Spring Grove), Loughton	Signal controlled crossing	High volumes crossing road at school times.	The width of the road may preclude a refuge, but there is good visibility at the site for a crossing. Although the 85th percentile speeds of traffic in below 30mph northbound, it is faster southbound and may not be deemed suitable for a zebra crossing. The volume of traffic is quite high at this location, but the majority of pedestrian activity is to and from the school. Assuming there is not a school crossing patrol solution to the peak hour demands, the interruption to traffic flow with a computerized signalized crossing would be restricted to these periods only. On the Strategic Network - will require specific sign off.	Historic scheme list	£170,000+ for the installation of a Puffin Crossing £10,000 feasibility study	9 months	Red
10	BH&LS	Loughton	Oakwood Hill j/w South View Road	Traffic calming	Vehicles driving across footway to avoid permanent traffic signals	Scheme Validation has suggested bollard across footway to prevent vehicles driving along it.	Residents/Co uncillors	£4,000	TBC	green

Division	Parish / Town Council	Location	Type of Scheme	Details of Scheme	Issues / Comments / Reason for Scheme	Scheme Origination	Approx. Timescale	Estimated Cost	Priority (RAG)
1	BH&LS	Loughton	BSI	Repaint the faded bus cages and bus markings on the road.	Existing markings and very worn and in need of refreshing.	Requested by TFL	3 months	£ 600.00	Amber

	Ref No.	Division	Parish / Town Council	Location	Proposed Solution	Timescale	Cost (£)	RAG
4	22	LC/BH&LS	Loughton	High Rd jw Forest Rd, Loughton	Parking enforcement, central island and ETP engagement, £5k cost split £2.5k between LC and BH&LS	TBC	5k	Green