Descriptions of works (as set out in 5 year Planned Maintenance Programme 2017/22 for Operational and Commercial Properties)	Project complete or to be completed by 31/03/18	Project delayed. Budget to roll forward to 2018/19	Project on hold pending outcome of accommodation review	Part of project on hold and part of project to be completed by 31/03/18
0.1.00				
Civic Offices				
Electrical/Mechanical Statutory testing of emergency lighting installations and rectification of defects.				
statutory testing of emergency lighting installations and rectification of defects.	P			
Statutory testing of electrical installation and rectification of defects - Electricity	P			
At Work Act.	r			
Replacement and repair of general items of electrical equipment/equipment nousing. This is generally in the external areas where equipment housing have begun to rust.			P	
Energy efficiency / CO2 reduction.			P	
Main Civic Building - Replacement of lighting with LED lighting.			P	
Electrical Intake Pyramid Building - Electrical load management and replace			P	
standby diesel generator. Main Civic Building - continued installation of smart meters to help monitor the council's energy usage and target areas for future energy saving			P	
enhancements.				
Main Civic Building - upgrade of fire alarm loops.	P			
Conder building - Replacement of the fire alarm amplifier rack. This equipment				
s approximately 25 years old and is now becoming a maintenance liability.	P			
Main Civic Building - Trend controller update (works associated with the eplacement of the AHUs. This is to keep Trend running and working with all new and replaced equipment)			P	
Main Civic Building - Upgrade and extension of Trend system to allow connection of all sheltered housing units to be monitored and controlled via	P			
he Trend system.			D	
Conder Building - Daikin interface upgrade. Homefield House - Upgrade fire alarm and power			P P	
Main Civic Building - Phased replacement of electrical power distribution				
equipment in all intakes due to life expiry and health and safety risk			P	
Main Civic Building - Phased replacement of electrical breakers and fuses in				P
electrical riser nos. 1, 2 & 3 due to life expiry and health & safety risk				r
Refurbish first floor tower toilets			P	
Refurbish ground floor tower toilets Main Civic Building - Fire alarm system - speaker replacement & new smoke & heat detection	P		P	
Main Civic Building - Phased replacement of electrical power distribution equipment in all the intakes			P	
Main Civic Building - Replacement of Mitsubishi air conditioning on the link oridge roof. Units are at the end of their serviceable life and have now			P	
pecome a maintenance liability Electrical Intake Pyramid Building - Installation of new generator main switch,				
inking to new bypass panel in advance of new generator			P	
Main Civic Building - Computer Suite 2 - replacement of air conditioning units			P	
Main Civic Building - Plant room 2 LARGE AHU replacement - Current fan is old and very inefficient - upgrade to efficient fan with variable volume control acility			P	
Main Civic Building - Replacement of the mechanical control panels. These panels have come to the end of their life span and require upgrading				P
Main Duilding				
Main Building Carry out isolated patch repairs to dense bitumen macadam surface in car	1			
oark 3 and seal surface cracking with liquid bitumen in car parks 2 and 3	P			
Carry out localised repointing of joints in stone external walls, ceremonial external staircase and various stone cill and render repairs identified at the time of specialist stone cleaning works to building elevations in 2016	P			
Jsing a mobile elevated working platform for safe working at height, carry out minor repointing works to brickwork over second floor lintels. Rake out and replace failed mastic joints to second floor stonework to part front elevation	P			
Repair to netting to prevent pigeons messing around air conditioning units. nclude for safe working at height			P	
Partial replacement of worn floor finishes to offices, common and public areas			P	
General "touch up" decoration to previously painted surfaces in public areas, circulation spaces and offices to ensure areas remain at a high aesthetic			P	
standard				
Redecorate room G.01 and room 1.20			P	
Jplift and replace worn and heavily soiled carpets in room G.01; room 1.12; coom 1.20; room 1.26			P	
Conder Building	i .		1	

	1	1	1	
General "touch up" decoration to previously painted surfaces circulation			P	
spaces and offices to ensure areas remain at a high aesthetic standard				
Partial replacement of suspended ceilings			P	
Replacement of dilapidated air conditioning cages in building car parks			P	
Hemnall Street Offices				
Isolated repair and redecoration of timber windows and barge boards to	P			
ensure weathertightness of these elements until full redecoration in 2019	_			
Overlay existing life expired mineral felt covering to single storey flat roof over	_			
rear open plan office area with a new single layer cap sheet. Allow for edge	P			
protection guardrails for safe working at height				
63 The Broadway Office	_			
Carry out redecoration of public entrance foyer area and interview room	P			
Brooker Road Industrial Estate				
Environmental maintenance - clear weeds, vegetation and litter from common	P			
areas, service roads and car parks	_			
Carry out isolated patch repairs to concrete parking aprons and drainage	P			
channels to service roads				
Clear all surface water road gullies to landlord's car parks and service roads				
to remove debris and any other obstructions. Jet through underground drains	P			
to ensure free flowing effective operation				
Oakwood Hill Industrial Estate				
Clear all surface water road gullies and drainage channels to remove debris	D.			
and any other obstructions. Jet through underground drains to ensure free	P			
flowing effective operation				
Install section of steel tubular post and rail fencing adjacent to height restriction barriers to prevent unauthorised entry in to car park	P			
Overhaul chain link fence to perimeter of car park	P			
Redecorate hazard markings to height restriction barriers	P			
Oakwood Hill Workshop Units	•			
Carry out environmental maintenance to clear weeds, vegetation and litter				
from roads, parking areas and fire exit routes	P			
Clear all surface water road gullies and drainage channels to remove debris				
and any other obstructions. Jet through underground drains to ensure free	P			
flowing effective operation	_			
Excavate and remove vehicle damaged sections of drainage channel and				
gratings. Install new heavy duty channels and gratings	P			
Epping Depot, Epping				
As the closure of this asset is imminent the buildings have not been surveyed				
and no specific planned maintenance works are therefore proposed				
and no specific planned maintenance works are increiore proposed				
A general provisional sum has been allowed to ensure that basic standards of	P			
repair are instigated to ensure that health and safety standards are met until	_			
formal closure.				
Townmead Depot				
Health and safety works				P
Options for redevelopment of this depot are currently being considered. Most				
Options for redevelopment of this depot are currently being considered. Most of the buildings on the site have well exceeded their design life and are well				
of the buildings on the site have well exceeded their design life and are well	p			
of the buildings on the site have well exceeded their design life and are well beyond economic repair. Whilst consideration is being given to the best way	P			
of the buildings on the site have well exceeded their design life and are well beyond economic repair. Whilst consideration is being given to the best way to develop the site, it is recommended that generally only health, safety and staff welfare works are undertaken	P			
of the buildings on the site have well exceeded their design life and are well beyond economic repair. Whilst consideration is being given to the best way to develop the site, it is recommended that generally only health, safety and staff welfare works are undertaken A general provisional sum has been allowed to ensure that basic standards of	P			
of the buildings on the site have well exceeded their design life and are well beyond economic repair. Whilst consideration is being given to the best way to develop the site, it is recommended that generally only health, safety and staff welfare works are undertaken A general provisional sum has been allowed to ensure that basic standards of repair are instigated until a decision is made.				
of the buildings on the site have well exceeded their design life and are well beyond economic repair. Whilst consideration is being given to the best way to develop the site, it is recommended that generally only health, safety and staff welfare works are undertaken A general provisional sum has been allowed to ensure that basic standards of repair are instigated until a decision is made. Clearance of vegetation and silt from Collara Brook watercourse	P P			
of the buildings on the site have well exceeded their design life and are well beyond economic repair. Whilst consideration is being given to the best way to develop the site, it is recommended that generally only health, safety and staff welfare works are undertaken A general provisional sum has been allowed to ensure that basic standards of repair are instigated until a decision is made. Clearance of vegetation and silt from Collara Brook watercourse Clear debris from all surface water gullies and to yard, and jet through surface	P			
of the buildings on the site have well exceeded their design life and are well beyond economic repair. Whilst consideration is being given to the best way to develop the site, it is recommended that generally only health, safety and staff welfare works are undertaken A general provisional sum has been allowed to ensure that basic standards of repair are instigated until a decision is made. Clearance of vegetation and silt from Collara Brook watercourse Clear debris from all surface water gullies and to yard, and jet through surface water drainage to leave free flowing. Jet through foul drains beyond the first				
of the buildings on the site have well exceeded their design life and are well beyond economic repair. Whilst consideration is being given to the best way to develop the site, it is recommended that generally only health, safety and staff welfare works are undertaken A general provisional sum has been allowed to ensure that basic standards of repair are instigated until a decision is made. Clearance of vegetation and silt from Collara Brook watercourse Clear debris from all surface water gullies and to yard, and jet through surface water drainage to leave free flowing. Jet through foul drains beyond the first external manholes of premises	P P			
of the buildings on the site have well exceeded their design life and are well beyond economic repair. Whilst consideration is being given to the best way to develop the site, it is recommended that generally only health, safety and staff welfare works are undertaken A general provisional sum has been allowed to ensure that basic standards of repair are instigated until a decision is made. Clearance of vegetation and silt from Collara Brook watercourse Clear debris from all surface water gullies and to yard, and jet through surface water drainage to leave free flowing. Jet through foul drains beyond the first external manholes of premises Environmental maintenance - clear weeds, vegetation and litter from common	P			
of the buildings on the site have well exceeded their design life and are well beyond economic repair. Whilst consideration is being given to the best way to develop the site, it is recommended that generally only health, safety and staff welfare works are undertaken A general provisional sum has been allowed to ensure that basic standards of repair are instigated until a decision is made. Clearance of vegetation and silt from Collara Brook watercourse Clear debris from all surface water gullies and to yard, and jet through surface water drainage to leave free flowing. Jet through foul drains beyond the first external manholes of premises Environmental maintenance - clear weeds, vegetation and litter from common areas, access roads and parking bays	P P			
of the buildings on the site have well exceeded their design life and are well beyond economic repair. Whilst consideration is being given to the best way to develop the site, it is recommended that generally only health, safety and staff welfare works are undertaken A general provisional sum has been allowed to ensure that basic standards of repair are instigated until a decision is made. Clearance of vegetation and silt from Collara Brook watercourse Clear debris from all surface water gullies and to yard, and jet through surface water drainage to leave free flowing. Jet through foul drains beyond the first external manholes of premises Environmental maintenance - clear weeds, vegetation and litter from common areas, access roads and parking bays Building 21 - To former WC area / canteen building, remove dilapidated water	P P			
of the buildings on the site have well exceeded their design life and are well beyond economic repair. Whilst consideration is being given to the best way to develop the site, it is recommended that generally only health, safety and staff welfare works are undertaken A general provisional sum has been allowed to ensure that basic standards of repair are instigated until a decision is made. Clearance of vegetation and silt from Collara Brook watercourse Clear debris from all surface water gullies and to yard, and jet through surface water drainage to leave free flowing. Jet through foul drains beyond the first external manholes of premises Environmental maintenance - clear weeds, vegetation and litter from common areas, access roads and parking bays Building 21 - To former WC area / canteen building, remove dilapidated water tank and timber housing structure located on roof. Make good roof covering	P P			
of the buildings on the site have well exceeded their design life and are well beyond economic repair. Whilst consideration is being given to the best way to develop the site, it is recommended that generally only health, safety and staff welfare works are undertaken A general provisional sum has been allowed to ensure that basic standards of repair are instigated until a decision is made. Clearance of vegetation and silt from Collara Brook watercourse Clear debris from all surface water gullies and to yard, and jet through surface water drainage to leave free flowing. Jet through foul drains beyond the first external manholes of premises Environmental maintenance - clear weeds, vegetation and litter from common areas, access roads and parking bays Building 21 - To former WC area / canteen building, remove dilapidated water	P P			
of the buildings on the site have well exceeded their design life and are well beyond economic repair. Whilst consideration is being given to the best way to develop the site, it is recommended that generally only health, safety and staff welfare works are undertaken A general provisional sum has been allowed to ensure that basic standards of repair are instigated until a decision is made. Clearance of vegetation and silt from Collara Brook watercourse Clear debris from all surface water gullies and to yard, and jet through surface water drainage to leave free flowing. Jet through foul drains beyond the first external manholes of premises Environmental maintenance - clear weeds, vegetation and litter from common areas, access roads and parking bays Building 21 - To former WC area / canteen building, remove dilapidated water tank and timber housing structure located on roof. Make good roof covering where housing removed in order to leave covering watertight. Allow for	P P P			
of the buildings on the site have well exceeded their design life and are well beyond economic repair. Whilst consideration is being given to the best way to develop the site, it is recommended that generally only health, safety and staff welfare works are undertaken A general provisional sum has been allowed to ensure that basic standards of repair are instigated until a decision is made. Clearance of vegetation and silt from Collara Brook watercourse Clear debris from all surface water gullies and to yard, and jet through surface water drainage to leave free flowing. Jet through foul drains beyond the first external manholes of premises Environmental maintenance - clear weeds, vegetation and litter from common areas, access roads and parking bays Building 21 - To former WC area / canteen building, remove dilapidated water tank and timber housing structure located on roof. Make good roof covering where housing removed in order to leave covering watertight. Allow for scaffolding access and bridging across fragile roof surface	P P P			
of the buildings on the site have well exceeded their design life and are well beyond economic repair. Whilst consideration is being given to the best way to develop the site, it is recommended that generally only health, safety and staff welfare works are undertaken A general provisional sum has been allowed to ensure that basic standards of repair are instigated until a decision is made. Clearance of vegetation and silt from Collara Brook watercourse Clear debris from all surface water gullies and to yard, and jet through surface water drainage to leave free flowing. Jet through foul drains beyond the first external manholes of premises Environmental maintenance - clear weeds, vegetation and litter from common areas, access roads and parking bays Building 21 - To former WC area / canteen building, remove dilapidated water tank and timber housing structure located on roof. Make good roof covering where housing removed in order to leave covering watertight. Allow for scaffolding access and bridging across fragile roof surface As a short term repair until life expired buildings are replaced, carry out repairs	P P P			
of the buildings on the site have well exceeded their design life and are well beyond economic repair. Whilst consideration is being given to the best way to develop the site, it is recommended that generally only health, safety and staff welfare works are undertaken A general provisional sum has been allowed to ensure that basic standards of repair are instigated until a decision is made. Clearance of vegetation and silt from Collara Brook watercourse Clear debris from all surface water gullies and to yard, and jet through surface water drainage to leave free flowing. Jet through foul drains beyond the first external manholes of premises Environmental maintenance - clear weeds, vegetation and litter from common areas, access roads and parking bays Building 21 - To former WC area / canteen building, remove dilapidated water tank and timber housing structure located on roof. Make good roof covering where housing removed in order to leave covering watertight. Allow for scaffolding access and bridging across fragile roof surface As a short term repair until life expired buildings are replaced, carry out repairs to perimeter fencing and boundary walls	P P P			
of the buildings on the site have well exceeded their design life and are well beyond economic repair. Whilst consideration is being given to the best way to develop the site, it is recommended that generally only health, safety and staff welfare works are undertaken A general provisional sum has been allowed to ensure that basic standards of repair are instigated until a decision is made. Clearance of vegetation and silt from Collara Brook watercourse Clear debris from all surface water gullies and to yard, and jet through surface water drainage to leave free flowing. Jet through foul drains beyond the first external manholes of premises Environmental maintenance - clear weeds, vegetation and litter from common areas, access roads and parking bays Building 21 - To former WC area / canteen building, remove dilapidated water tank and timber housing structure located on roof. Make good roof covering where housing removed in order to leave covering watertight. Allow for scaffolding access and bridging across fragile roof surface As a short term repair until life expired buildings are replaced, carry out repairs to perimeter fencing and boundary walls Oakwood Hill Depot	P P P			
of the buildings on the site have well exceeded their design life and are well beyond economic repair. Whilst consideration is being given to the best way to develop the site, it is recommended that generally only health, safety and staff welfare works are undertaken A general provisional sum has been allowed to ensure that basic standards of repair are instigated until a decision is made. Clearance of vegetation and silt from Collara Brook watercourse Clear debris from all surface water gullies and to yard, and jet through surface water drainage to leave free flowing. Jet through foul drains beyond the first external manholes of premises Environmental maintenance - clear weeds, vegetation and litter from common areas, access roads and parking bays Building 21 - To former WC area / canteen building, remove dilapidated water tank and timber housing structure located on roof. Make good roof covering where housing removed in order to leave covering watertight. Allow for scaffolding access and bridging across fragile roof surface As a short term repair until life expired buildings are replaced, carry out repairs to perimeter fencing and boundary walls Oakwood Hill Depot To whole complex, jet through all foul and surface water drains to leave free	P P P			
of the buildings on the site have well exceeded their design life and are well beyond economic repair. Whilst consideration is being given to the best way to develop the site, it is recommended that generally only health, safety and staff welfare works are undertaken A general provisional sum has been allowed to ensure that basic standards of repair are instigated until a decision is made. Clearance of vegetation and silt from Collara Brook watercourse Clear debris from all surface water gullies and to yard, and jet through surface water drainage to leave free flowing. Jet through foul drains beyond the first external manholes of premises Environmental maintenance - clear weeds, vegetation and litter from common areas, access roads and parking bays Building 21 - To former WC area / canteen building, remove dilapidated water tank and timber housing structure located on roof. Make good roof covering where housing removed in order to leave covering watertight. Allow for scaffolding access and bridging across fragile roof surface As a short term repair until life expired buildings are replaced, carry out repairs to perimeter fencing and boundary walls Oakwood Hill Depot To whole complex, jet through all foul and surface water drains to leave free flowing, and empty petrol interceptors, catchpits, channels and road gullies Ongar Leisure Centre	P P P			
of the buildings on the site have well exceeded their design life and are well beyond economic repair. Whilst consideration is being given to the best way to develop the site, it is recommended that generally only health, safety and staff welfare works are undertaken A general provisional sum has been allowed to ensure that basic standards of repair are instigated until a decision is made. Clearance of vegetation and silt from Collara Brook watercourse Clear debris from all surface water gullies and to yard, and jet through surface water drainage to leave free flowing. Jet through foul drains beyond the first external manholes of premises Environmental maintenance - clear weeds, vegetation and litter from common areas, access roads and parking bays Building 21 - To former WC area / canteen building, remove dilapidated water tank and timber housing structure located on roof. Make good roof covering where housing removed in order to leave covering watertight. Allow for scaffolding access and bridging across fragile roof surface As a short term repair until life expired buildings are replaced, carry out repairs to perimeter fencing and boundary walls Oakwood Hill Depot To whole complex, jet through all foul and surface water drains to leave free flowing, and empty petrol interceptors, catchpits, channels and road gullies	P P P P			
of the buildings on the site have well exceeded their design life and are well beyond economic repair. Whilst consideration is being given to the best way to develop the site, it is recommended that generally only health, safety and staff welfare works are undertaken A general provisional sum has been allowed to ensure that basic standards of repair are instigated until a decision is made. Clearance of vegetation and silt from Collara Brook watercourse Clear debris from all surface water gullies and to yard, and jet through surface water drainage to leave free flowing. Jet through foul drains beyond the first external manholes of premises Environmental maintenance - clear weeds, vegetation and litter from common areas, access roads and parking bays Building 21 - To former WC area / canteen building, remove dilapidated water tank and timber housing structure located on roof. Make good roof covering where housing removed in order to leave covering watertight. Allow for scaffolding access and bridging across fragile roof surface As a short term repair until life expired buildings are replaced, carry out repairs to perimeter fencing and boundary walls Oakwood Hill Depot To whole complex, jet through all foul and surface water drains to leave free flowing, and empty petrol interceptors, catchpits, channels and road gullies Ongar Leisure Centre	P P P			
of the buildings on the site have well exceeded their design life and are well beyond economic repair. Whilst consideration is being given to the best way to develop the site, it is recommended that generally only health, safety and staff welfare works are undertaken A general provisional sum has been allowed to ensure that basic standards of repair are instigated until a decision is made. Clearance of vegetation and silt from Collara Brook watercourse Clear debris from all surface water gullies and to yard, and jet through surface water drainage to leave free flowing. Jet through foul drains beyond the first external manholes of premises Environmental maintenance - clear weeds, vegetation and litter from common areas, access roads and parking bays Building 21 - To former WC area / canteen building, remove dilapidated water tank and timber housing structure located on roof. Make good roof covering where housing removed in order to leave covering watertight. Allow for scaffolding access and bridging across fragile roof surface As a short term repair until life expired buildings are replaced, carry out repairs to perimeter fencing and boundary walls Oakwood Hill Depot To whole complex, jet through all foul and surface water drains to leave free flowing, and empty petrol interceptors, catchpits, channels and road gullies Ongar Leisure Centre Clear all gullies and jet through surface water drains to yards, car parks and walkways including emptying petrol interceptors and cleaning filters	P P P P			
of the buildings on the site have well exceeded their design life and are well beyond economic repair. Whilst consideration is being given to the best way to develop the site, it is recommended that generally only health, safety and staff welfare works are undertaken A general provisional sum has been allowed to ensure that basic standards of repair are instigated until a decision is made. Clearance of vegetation and silt from Collara Brook watercourse Clear debris from all surface water gullies and to yard, and jet through surface water drainage to leave free flowing. Jet through foul drains beyond the first external manholes of premises Environmental maintenance - clear weeds, vegetation and litter from common areas, access roads and parking bays Building 21 - To former WC area / canteen building, remove dilapidated water tank and timber housing structure located on roof. Make good roof covering where housing removed in order to leave covering watertight. Allow for scaffolding access and bridging across fragile roof surface As a short term repair until life expired buildings are replaced, carry out repairs to perimeter fencing and boundary walls Oakwood Hill Depot To whole complex, jet through all foul and surface water drains to leave free flowing, and empty petrol interceptors, catchpits, channels and road gullies Ongar Leisure Centre Clear all gullies and jet through surface water drains to yards, car parks and walkways including emptying petrol interceptors and cleaning filters Nursery, Pyrles Lane, Loughton	P P P P			
of the buildings on the site have well exceeded their design life and are well beyond economic repair. Whilst consideration is being given to the best way to develop the site, it is recommended that generally only health, safety and staff welfare works are undertaken A general provisional sum has been allowed to ensure that basic standards of repair are instigated until a decision is made. Clearance of vegetation and silt from Collara Brook watercourse Clear debris from all surface water gullies and to yard, and jet through surface water drainage to leave free flowing. Jet through foul drains beyond the first external manholes of premises Environmental maintenance - clear weeds, vegetation and litter from common areas, access roads and parking bays Building 21 - To former WC area / canteen building, remove dilapidated water tank and timber housing structure located on roof. Make good roof covering where housing removed in order to leave covering watertight. Allow for scaffolding access and bridging across fragile roof surface As a short term repair until life expired buildings are replaced, carry out repairs to perimeter fencing and boundary walls Oakwood Hill Depot To whole complex, jet through all foul and surface water drains to leave free flowing, and empty petrol interceptors, catchpits, channels and road gullies Ongar Leisure Centre Clear all gullies and jet through surface water drains to yards, car parks and walkways including emptying petrol interceptors and cleaning filters	P P P P			
of the buildings on the site have well exceeded their design life and are well beyond economic repair. Whilst consideration is being given to the best way to develop the site, it is recommended that generally only health, safety and staff welfare works are undertaken A general provisional sum has been allowed to ensure that basic standards of repair are instigated until a decision is made. Clearance of vegetation and silt from Collara Brook watercourse Clear debris from all surface water gullies and to yard, and jet through surface water drainage to leave free flowing. Jet through foul drains beyond the first external manholes of premises Environmental maintenance - clear weeds, vegetation and litter from common areas, access roads and parking bays Building 21 - To former WC area / canteen building, remove dilapidated water tank and timber housing structure located on roof. Make good roof covering where housing removed in order to leave covering watertight. Allow for scaffolding access and bridging across fragile roof surface As a short term repair until life expired buildings are replaced, carry out repairs to perimeter fencing and boundary walls Oakwood Hill Depot To whole complex, jet through all foul and surface water drains to leave free flowing, and empty petrol interceptors, catchpits, channels and road gullies Ongar Leisure Centre Clear all gullies and jet through surface water drains to yards, car parks and walkways including emptying petrol interceptors and cleaning filters Nursery, Pyrles Lane, Loughton As the closure of this asset is imminent, the buildings have not been surveyed	P P P P			
of the buildings on the site have well exceeded their design life and are well beyond economic repair. Whilst consideration is being given to the best way to develop the site, it is recommended that generally only health, safety and staff welfare works are undertaken A general provisional sum has been allowed to ensure that basic standards of repair are instigated until a decision is made. Clearance of vegetation and silt from Collara Brook watercourse Clear debris from all surface water gullies and to yard, and jet through surface water drainage to leave free flowing. Jet through foul drains beyond the first external manholes of premises Environmental maintenance - clear weeds, vegetation and litter from common areas, access roads and parking bays Building 21 - To former WC area / canteen building, remove dilapidated water tank and timber housing structure located on roof. Make good roof covering where housing removed in order to leave covering watertight. Allow for scaffolding access and bridging across fragile roof surface As a short term repair until life expired buildings are replaced, carry out repairs to perimeter fencing and boundary walls Oakwood Hill Depot To whole complex, jet through all foul and surface water drains to leave free flowing, and empty petrol interceptors, catchpits, channels and road gullies Ongar Leisure Centre Clear all gullies and jet through surface water drains to yards, car parks and walkways including emptying petrol interceptors and cleaning filters Nursery, Pyrles Lane, Loughton As the closure of this asset is imminent, the buildings have not been surveyed	P P P P			
of the buildings on the site have well exceeded their design life and are well beyond economic repair. Whilst consideration is being given to the best way to develop the site, it is recommended that generally only health, safety and staff welfare works are undertaken A general provisional sum has been allowed to ensure that basic standards of repair are instigated until a decision is made. Clearance of vegetation and silt from Collara Brook watercourse Clear debris from all surface water gullies and to yard, and jet through surface water drainage to leave free flowing. Jet through foul drains beyond the first external manholes of premises Environmental maintenance - clear weeds, vegetation and litter from common areas, access roads and parking bays Building 21 - To former WC area / canteen building, remove dilapidated water tank and timber housing structure located on roof. Make good roof covering where housing removed in order to leave covering watertight. Allow for scaffolding access and bridging across fragile roof surface As a short term repair until life expired buildings are replaced, carry out repairs to perimeter fencing and boundary walls Oakwood Hill Depot To whole complex, jet through all foul and surface water drains to leave free flowing, and empty petrol interceptors, catchpits, channels and road gullies Ongar Leisure Centre Clear all gullies and jet through surface water drains to yards, car parks and walkways including emptying petrol interceptors and cleaning filters Nursery, Pyrles Lane, Loughton As the closure of this asset is imminent, the buildings have not been surveyed and no specific planned maintenance works are therefore proposed	P P P P			
of the buildings on the site have well exceeded their design life and are well beyond economic repair. Whilst consideration is being given to the best way to develop the site, it is recommended that generally only health, safety and staff welfare works are undertaken A general provisional sum has been allowed to ensure that basic standards of repair are instigated until a decision is made. Clearance of vegetation and silt from Collara Brook watercourse Clear debris from all surface water gullies and to yard, and jet through surface water drainage to leave free flowing. Jet through foul drains beyond the first external manholes of premises Environmental maintenance - clear weeds, vegetation and litter from common areas, access roads and parking bays Building 21 - To former WC area / canteen building, remove dilapidated water tank and timber housing structure located on roof. Make good roof covering where housing removed in order to leave covering watertight. Allow for scaffolding access and bridging across fragile roof surface As a short term repair until life expired buildings are replaced, carry out repairs to perimeter fencing and boundary walls Oakwood Hill Depot To whole complex, jet through all foul and surface water drains to leave free flowing, and empty petrol interceptors, catchpits, channels and road gullies Ongar Leisure Centre Clear all gullies and jet through surface water drains to yards, car parks and walkways including emptying petrol interceptors and cleaning filters Nursery, Pyrles Lane, Loughton As the closure of this asset is imminent, the buildings have not been surveyed and no specific planned maintenance works are therefore proposed	P P P P			

Museum, Waltham Abbey To remedy defects identified during recent refurbishment works, scaffold out premises for safe working at height. Re-roof two storey pitched areas, including installing a breathable waterproof underlay membrane beneath tiles as there is currently no underlay at all below tiles. Provide new battens and replace all broken tiles. Reform all flashings, details and abutments. Provide insulation to roof spaces as required under Building Regulations Making use of scaffolding for roof works, access chimney stacks and repoint. Repair, re-render and redecorate where necessary. Repair / replace damaged chimney pots and re-flaunch. Overhaul lead flashings and details External redecoration of front, side and rear elevations; means of escape staircase including provision of anti-slip finish to treads and landing; external gates and railings. Include for access scaffolding and equipment for safe working at height Carry out improvements to surface water drainage within the courtyard garden area to dissipate rainwater away from the building and to assist with reducing water penetration into the ground floor gallery area where the damp proof course is minimal Jet through foul and surface water drains to remove obstructions and ensure free flowing Overhaul first floor windows in front gallery and rear offices areas including replacing balancers to each sash and general window ironmongery Touche the described with the store in disclass and elevation.	
To remedy defects identified during recent refurbishment works, scaffold out premises for safe working at height. Re-roof two storey pitched areas, including installing a breathable waterproof underlay membrane beneath tiles as there is currently no underlay at all below tiles. Provide new battens and replace all broken tiles. Reform all flashings, details and abutments. Provide insulation to roof spaces as required under Building Regulations Making use of scaffolding for roof works, access chimney stacks and repoint. Repair, re-render and redecorate where necessary. Repair / replace damaged chimney pots and re-flaunch. Overhaul lead flashings and details External redecoration of front, side and rear elevations; means of escape staircase including provision of anti-slip finish to treads and landing; external gates and railings. Include for access scaffolding and equipment for safe working at height Carry out improvements to surface water drainage within the courtyard garden area to dissipate rainwater away from the building and to assist with reducing water penetration into the ground floor gallery area where the damp proof course is minimal Jet through foul and surface water drains to remove obstructions and ensure free flowing Overhaul first floor windows in front gallery and rear offices areas including replacing balancers to each sash and general window ironmongery	
premises for safe working at height. Re-roof two storey pitched areas, including installing a breathable waterproof underlay membrane beneath tiles as there is currently no underlay at all below tiles. Provide new battens and replace all broken tiles. Reform all flashings, details and abutments. Provide insulation to roof spaces as required under Building Regulations Making use of scaffolding for roof works, access chimney stacks and repoint. Repair, re-render and redecorate where necessary. Repair / replace damaged chimney pots and re-flaunch. Overhaul lead flashings and details External redecoration of front, side and rear elevations; means of escape staircase including provision of anti-slip finish to treads and landing; external gates and railings. Include for access scaffolding and equipment for safe working at height Carry out improvements to surface water drainage within the courtyard garden area to dissipate rainwater away from the building and to assist with reducing water penetration into the ground floor gallery area where the damp proof course is minimal Jet through foul and surface water drains to remove obstructions and ensure free flowing Overhaul first floor windows in front gallery and rear offices areas including replacing balancers to each sash and general window ironmongery	
including installing a breathable waterproof underlay membrane beneath tiles as there is currently no underlay at all below tiles. Provide new battens and replace all broken tiles. Reform all flashings, details and abutments. Provide insulation to roof spaces as required under Building Regulations Making use of scaffolding for roof works, access chimney stacks and repoint. Repair, re-render and redecorate where necessary. Repair / replace damaged chimney pots and re-flaunch. Overhaul lead flashings and details External redecoration of front, side and rear elevations; means of escape staircase including provision of anti-slip finish to treads and landing; external gates and railings. Include for access scaffolding and equipment for safe working at height Carry out improvements to surface water drainage within the courtyard garden area to dissipate rainwater away from the building and to assist with reducing water penetration into the ground floor gallery area where the damp proof course is minimal Jet through foul and surface water drains to remove obstructions and ensure free flowing Overhaul first floor windows in front gallery and rear offices areas including replacing balancers to each sash and general window ironmongery	
as there is currently no underlay at all below tiles. Provide new battens and replace all broken tiles. Reform all flashings, details and abutments. Provide insulation to roof spaces as required under Building Regulations Making use of scaffolding for roof works, access chimney stacks and repoint. Repair, re-render and redecorate where necessary. Repair / replace damaged chimney pots and re-flaunch. Overhaul lead flashings and details External redecoration of front, side and rear elevations; means of escape staircase including provision of anti-slip finish to treads and landing; external gates and railings. Include for access scaffolding and equipment for safe working at height Carry out improvements to surface water drainage within the courtyard garden area to dissipate rainwater away from the building and to assist with reducing water penetration into the ground floor gallery area where the damp proof course is minimal Jet through foul and surface water drains to remove obstructions and ensure free flowing Overhaul first floor windows in front gallery and rear offices areas including replacing balancers to each sash and general window ironmongery	
replace all broken tiles. Reform all flashings, details and abutments. Provide insulation to roof spaces as required under Building Regulations Making use of scaffolding for roof works, access chimney stacks and repoint. Repair, re-render and redecorate where necessary. Repair / replace damaged chimney pots and re-flaunch. Overhaul lead flashings and details External redecoration of front, side and rear elevations; means of escape staircase including provision of anti-slip finish to treads and landing; external gates and railings. Include for access scaffolding and equipment for safe working at height Carry out improvements to surface water drainage within the courtyard garden area to dissipate rainwater away from the building and to assist with reducing water penetration into the ground floor gallery area where the damp proof course is minimal Jet through foul and surface water drains to remove obstructions and ensure free flowing Overhaul first floor windows in front gallery and rear offices areas including replacing balancers to each sash and general window ironmongery	
insulation to roof spaces as required under Building Regulations Making use of scaffolding for roof works, access chimney stacks and repoint. Repair, re-render and redecorate where necessary. Repair / replace damaged chimney pots and re-flaunch. Overhaul lead flashings and details External redecoration of front, side and rear elevations; means of escape staircase including provision of anti-slip finish to treads and landing; external gates and railings. Include for access scaffolding and equipment for safe working at height Carry out improvements to surface water drainage within the courtyard garden area to dissipate rainwater away from the building and to assist with reducing water penetration into the ground floor gallery area where the damp proof course is minimal Jet through foul and surface water drains to remove obstructions and ensure free flowing Overhaul first floor windows in front gallery and rear offices areas including replacing balancers to each sash and general window ironmongery	
Making use of scaffolding for roof works, access chimney stacks and repoint. Repair, re-render and redecorate where necessary. Repair / replace damaged chimney pots and re-flaunch. Overhaul lead flashings and details External redecoration of front, side and rear elevations; means of escape staircase including provision of anti-slip finish to treads and landing; external gates and railings. Include for access scaffolding and equipment for safe working at height Carry out improvements to surface water drainage within the courtyard garden area to dissipate rainwater away from the building and to assist with reducing water penetration into the ground floor gallery area where the damp proof course is minimal Jet through foul and surface water drains to remove obstructions and ensure free flowing Overhaul first floor windows in front gallery and rear offices areas including replacing balancers to each sash and general window ironmongery	
Repair, re-render and redecorate where necessary. Repair / replace damaged chimney pots and re-flaunch. Overhaul lead flashings and details External redecoration of front, side and rear elevations; means of escape staircase including provision of anti-slip finish to treads and landing; external gates and railings. Include for access scaffolding and equipment for safe working at height Carry out improvements to surface water drainage within the courtyard garden area to dissipate rainwater away from the building and to assist with reducing water penetration into the ground floor gallery area where the damp proof course is minimal Jet through foul and surface water drains to remove obstructions and ensure free flowing Overhaul first floor windows in front gallery and rear offices areas including replacing balancers to each sash and general window ironmongery	
Repair, re-render and redecorate where necessary. Repair / replace damaged chimney pots and re-flaunch. Overhaul lead flashings and details External redecoration of front, side and rear elevations; means of escape staircase including provision of anti-slip finish to treads and landing; external gates and railings. Include for access scaffolding and equipment for safe working at height Carry out improvements to surface water drainage within the courtyard garden area to dissipate rainwater away from the building and to assist with reducing water penetration into the ground floor gallery area where the damp proof course is minimal Jet through foul and surface water drains to remove obstructions and ensure free flowing Overhaul first floor windows in front gallery and rear offices areas including replacing balancers to each sash and general window ironmongery	
damaged chimney pots and re-flaunch. Overhaul lead flashings and details External redecoration of front, side and rear elevations; means of escape staircase including provision of anti-slip finish to treads and landing; external gates and railings. Include for access scaffolding and equipment for safe working at height Carry out improvements to surface water drainage within the courtyard garden area to dissipate rainwater away from the building and to assist with reducing water penetration into the ground floor gallery area where the damp proof course is minimal Jet through foul and surface water drains to remove obstructions and ensure free flowing Overhaul first floor windows in front gallery and rear offices areas including replacing balancers to each sash and general window ironmongery	
External redecoration of front, side and rear elevations; means of escape staircase including provision of anti-slip finish to treads and landing; external gates and railings. Include for access scaffolding and equipment for safe working at height Carry out improvements to surface water drainage within the courtyard garden area to dissipate rainwater away from the building and to assist with reducing water penetration into the ground floor gallery area where the damp proof course is minimal Jet through foul and surface water drains to remove obstructions and ensure free flowing Overhaul first floor windows in front gallery and rear offices areas including replacing balancers to each sash and general window ironmongery	
staircase including provision of anti-slip finish to treads and landing; external gates and railings. Include for access scaffolding and equipment for safe working at height Carry out improvements to surface water drainage within the courtyard garden area to dissipate rainwater away from the building and to assist with reducing water penetration into the ground floor gallery area where the damp proof course is minimal Jet through foul and surface water drains to remove obstructions and ensure free flowing Overhaul first floor windows in front gallery and rear offices areas including replacing balancers to each sash and general window ironmongery	
staircase including provision of anti-slip finish to treads and landing; external gates and railings. Include for access scaffolding and equipment for safe working at height Carry out improvements to surface water drainage within the courtyard garden area to dissipate rainwater away from the building and to assist with reducing water penetration into the ground floor gallery area where the damp proof course is minimal Jet through foul and surface water drains to remove obstructions and ensure free flowing Overhaul first floor windows in front gallery and rear offices areas including replacing balancers to each sash and general window ironmongery	
gates and railings. Include for access scaffolding and equipment for safe working at height Carry out improvements to surface water drainage within the courtyard garden area to dissipate rainwater away from the building and to assist with reducing water penetration into the ground floor gallery area where the damp proof course is minimal Jet through foul and surface water drains to remove obstructions and ensure free flowing Overhaul first floor windows in front gallery and rear offices areas including replacing balancers to each sash and general window ironmongery	
gates and railings. Include for access scaffolding and equipment for safe working at height Carry out improvements to surface water drainage within the courtyard garden area to dissipate rainwater away from the building and to assist with reducing water penetration into the ground floor gallery area where the damp proof course is minimal Jet through foul and surface water drains to remove obstructions and ensure free flowing Overhaul first floor windows in front gallery and rear offices areas including replacing balancers to each sash and general window ironmongery	
working at height Carry out improvements to surface water drainage within the courtyard garden area to dissipate rainwater away from the building and to assist with reducing water penetration into the ground floor gallery area where the damp proof course is minimal Jet through foul and surface water drains to remove obstructions and ensure free flowing Overhaul first floor windows in front gallery and rear offices areas including replacing balancers to each sash and general window ironmongery	
Carry out improvements to surface water drainage within the courtyard garden area to dissipate rainwater away from the building and to assist with reducing water penetration into the ground floor gallery area where the damp proof course is minimal Jet through foul and surface water drains to remove obstructions and ensure free flowing Overhaul first floor windows in front gallery and rear offices areas including replacing balancers to each sash and general window ironmongery	
area to dissipate rainwater away from the building and to assist with reducing water penetration into the ground floor gallery area where the damp proof course is minimal Jet through foul and surface water drains to remove obstructions and ensure free flowing Overhaul first floor windows in front gallery and rear offices areas including replacing balancers to each sash and general window ironmongery	
water penetration into the ground floor gallery area where the damp proof course is minimal Jet through foul and surface water drains to remove obstructions and ensure free flowing Overhaul first floor windows in front gallery and rear offices areas including replacing balancers to each sash and general window ironmongery	
course is minimal Jet through foul and surface water drains to remove obstructions and ensure free flowing Overhaul first floor windows in front gallery and rear offices areas including replacing balancers to each sash and general window ironmongery	
Jet through foul and surface water drains to remove obstructions and ensure free flowing Overhaul first floor windows in front gallery and rear offices areas including replacing balancers to each sash and general window ironmongery	
free flowing Overhaul first floor windows in front gallery and rear offices areas including replacing balancers to each sash and general window ironmongery	
tree flowing Overhaul first floor windows in front gallery and rear offices areas including replacing balancers to each sash and general window ironmongery	
replacing balancers to each sash and general window ironmongery	
replacing balancers to each sash and general window ironmongery	
Touch up descrition to well surfaces in display colleges and sirgulation	
Touch up decoration to wall surfaces in display galleries and circulation	
spaces to ensure visitor areas remain at a high aesthetic standard	
North Weald Airfield, North Weald	
Gatehouse	
Penlace dilapidated single glazed timber windows, doors and reeffights with	
new thermally efficient double glazed aluminium units	
Carry out external redecoration of timber surfaces, metal gates and railings	
Internal redecoration of offices and common areas P	
Control Tower	
Prior to redecoration, pressure wash foot trafficked roof areas and balconies	
to remove grime and slip hazards. Allow for minor top up coating repairs to P	
flashings, upstands and details	
Carry out external redecoration to concrete, masonry and metalwork surfaces	
including safe access equipment for working at height	
As requested by airfield operations officers, install energy efficient wall	
mounted instant boiling water appliances in ground floor conference room	
kitchen area and first floor kitchen to enable conference attendees to access	
quick and easy tea and coffee making facilities	
Gymnastics Centre	
Maintenance of fire escape routes including clearance of vegetation from	
external fire escape routes and from around access road and car park	
Clear debris from all gullies and drainage channels to car park, access road	
and external areas and jet through surface water drainage to leave free P	
flowing	
Annexe to Hangar 1	
External redecoration of fascias, soffits, doors and panels	
The Limes Centre	
Wash down external plastisol coated soffits and fascias and powder coated	
windows and doors. Redecorate external rendered elevations and metal	
railings. Include for access scaffolding and equipment for safe working at	
height	
Reconstruct underground foul drains / enlarge access manhole serving main	
toilet areas to prevent ongoing blockages. Allow to uplift and relay entrance	
paving slabs to facilitate	
Jet through foul and surface water drains to remove obstructions and ensure	
free flowing	
Pressure wash naving slah footnaths, ramps, steps and public general	
circulation spaces to restore surface finishes	
Insert maintenance inspection batches into air handling ductwork to facilitate	
ongoing cleaning	
Clean all air handling, ductwork to remove duct and debric and provent	
microbiological contamination	
Ongar Public Toilets	
Jet through foul and surface water drains to remove obstructions and ensure	
rree flowing	
Prepare and redecorate previously painted external surfaces and internal	
ceilings	
Business Premises	
General	
General fund share of works carried out by Communities Directorate to shops	
where there are shared maintenance liabilities.	
Borders Lane, Loughton (58 to 76)	
Environmental maintenance - clear weeds, vegetation and litter from common	
areas and service road	
Clear debris from all surface water gullies to yards and jet through surface	
water drainage to leave free flowing. Jet through foul drains beyond the first P	
external manholes of premises	

	T	T	T	T
Hillhouse, Waltham Abbey (1 to 12)				
Clear debris from all surface water gullies and drainage channels to yards and				
car park. Empty petrol interceptors and jet through surface water drainage to	P			
leave free flowing. Jet through foul drains beyond the first external manholes	-			
of premises				
Limes Avenue, Chigwell (548 to 562 including covered walkway and				
common areas)				
Carry out pressure washing and general maintenance of undercover paved				
areas and environmental maintenance to clear weeds, vegetation and litter	P			
from common areas, yard, car park and walkways.				
Clear debris from all surface water gullies and drainage channels to yards and	ъ			
car park and jet through surface water drainage to leave free flowing. Jet	P			
through foul drains beyond the first external manholes of premises				
Loughton Way, Buckhurst Hill (142 to 164)				
Environmental maintenance - clear weeds, vegetation and litter from common areas and strim grass bank	P			
Market Square, Waltham Abbey (15 to 19)				
Clear debris from all surface water gullies to yards and common areas and jet				
through surface water drainage to leave free flowing. Jet through foul drains	P			
beyond the first external manhole of each premises	•			
Parklands Coopersale (28 to 31)				
Environmental maintenance - clear weeds, vegetation and litter from common				
areas and service yard	P			
Clear debris from all surface water gullies to service yard and jet through	_			
surface water drainage to leave free flowing	P			
Pyrles Lane, Loughton (34 to 52)				
Clear debris from all surface water gullies and drainage channels to yards and				
car park. Empty petrol interceptor and jet through surface water drainage to	P			
leave free flowing. Jet through foul drains beyond the first external manholes	P			
of premises				
Roundhills, Waltham Abbey (74 to 82)				
Clean diffusers and change lamps to landlord's lighting under front canopy, to	P			
yards and side elevation				
Redecoration of front canopy, side elevation, common areas and bollards	P			
Clear debris from all surface water gullies and drainage channels to service				
yard and common areas and jet through surface water drainage to leave free	P			
flowing. Jet through foul drains beyond the first external manholes of	_			
premises				
The Broadway, Loughton (11 to 73 & 12 to 82)				
To various single storey flat roofs, overlay existing life expired mineral felt				
coverings with a new single layer cap sheet and/or apply a high performance				
polyurethane coating system to life expired asphalt surfaces. Allow for				P
isolated repairs to coping stones and external brick walls where damaged and renew failing rainwater goods. Allow for edge protection guardrails for safe				
working at height. (16,18,20,26,52,&80)				
Environmental maintenance - clear weeds, vegetation and litter from common				
areas	P			
Replace 2 Nr life expired roller shutters to undercover public access walkway	_			
adjacent to shop 42	P			
Replace aging landlord's lighting to undercover public access walkway				
adjacent to shop 42 with new energy efficient, vandal resistant LED light	P			
fittings				
Redecorate walls and ceiling to undercover public access walkway adjacent				
shop to 42. Clean and prepare floor and apply a two pack epoxy anti-slip floor	P			
coating				
The Street, High Ongar (48 & 50)		-		
Carry out external redecoration of rendered walls, timber and metalwork				
including renewal of anti slip coating to external fire escape staircase. Allow				
for minor overhaul of any loose / slipped roof tiles whilst on site and repointing	P			
at ridge. Allow for scaffolding for safe access when working at height				
Upshire Road, Waltham Abbey (113 to 123)				
Environmental maintenance - clear weeds, vegetation and litter from common	P			
areas				
Replace aging landlord's lighting to front elevation with new energy efficient,	P			
vandal resistant LED light fittings				
General Improvement Areas				
Alfred Road, Buckhurst Hill				
Environmental maintenance - clear weeds, vegetation and litter from common	P			
areas, access roads and parking bays To all areas - Clear all surface water road gullies and drainage channels to				
remove debris and any other obstructions. Jet through underground drains to	P			
ensure free flowing effective operation	•			
Woollard Street, Waltham Abbey				
Environmental maintenance - clear weeds, vegetation and litter from common	_			
areas and access roads	P			
To all areas - Clear all surface water road gullies to remove debris and any				
other obstructions. Jet through underground drains to ensure free flowing	P			
effective operation				
Emergency Repairs	P			
		_		